

MATERIAL LIST

G1818B Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	103.13	16"	45	EA
2	MAIN TREATED SILL		2X4			60	LF
3	MAIN EXT PLATES		2X4			135	LF
4	HEADER, (Ext Main Garage Door)	B01	4X12	10'		1	EA
5	HEADER, (Ext Main Door)	N/A	4X6	4'		1	EA
6	HEADER, (Main Window)	N/A	4X6	4'		1	EA
7	RAFTERS		2X6	11'	16"	29	EA
8	EAVE BLOCKING		2X	14.0"	16"	27	EA
9	H2.5 RAFTER TIE				16"	29	EA
10	ROOF SHEATH		1/2" CDX			404	SF
11	ROOF FELT		30# Felt			404	SF
12	ROOFING					404	SF
13	BARGE RAFTERS		2X6	11'		4	EA
14	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			540	SF
15	MAIN CEILING S.R. (Optional)		1/2" GYP.			324	SF
16	EXT WALL SHEATH		1/2" CDX			540	SF
17	EXT WALL VAPOR		15# Felt			540	SF
18	EXT SIDING (See Plan)		Varies			540	SF
19	CONCRETE					8.64	CY
20	JOISTS		2X10	18'	16"	14	EA
21	RIDGE BEAM		(SEE PLAN)	18'		1	EA
22	ANCHOR BOLTS		1/2"		48"	15	EA
23	HOLD DOWNS		HD2A W/SSTB16			4	EA
24	WIRE MESH		6X6 W1.4 X W1.4			324	SF

22685 S.W. Conifer Dr. Sherwood OR 97140

Internet: www.cadnw.com Email: cadnw@zzz.com (503) 625-6330 Voice



MATERIAL LIST

G1818B Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	103.13	16"	45	EA
2	MAIN TREATED SILL		2X4			60	LF
3	MAIN EXT PLATES		2X4			135	LF
4	HEADER, (Ext Main Garage Door)	B01	4X12	10'		1	EA
5	HEADER, (Ext Main Door)	N/A	4X6	4'		1	EA
6	HEADER, (Main Window)	N/A	4X6	4'		1	EA
7	TRUSSES				24"	8	EA
8	TRUSSES (Ends)					2	EA
9	EAVE BLOCKING		2X	22.0"	24"	18	EA
10	H2.5 RAFTER TIE				24"	20	EA
11	ROOF SHEATH		1/2" CDX			404	SF
12	ROOF FELT		30# Felt			404	SF
13	ROOFING					404	SF
14	BARGE RAFTERS		2X6	11'		4	EA
15	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			540	SF
16	MAIN CEILING S.R. (Optional)		1/2" GYP.			324	SF
17	EXT WALL SHEATH		1/2" CDX			540	SF
18	EXT WALL VAPOR		15# Felt			540	SF
19	EXT SIDING (See Plan)		Varies			540	SF
20	CONCRETE					8.64	CY
21	ANCHOR BOLTS		1/2"		48"	15	EA
22	HOLD DOWNS		HD2A W/SSTB16			4	EA
23	WIRE MESH		6X6 W1.4 X W1.4			324	SF

22685 S.W. Conifer Dr. Sherwood OR 97140

Internet: www.cadnw.com Email: cadnw@zzz.com (503) 625-6330 Voice