Custom Home Design CAD NorthWest

MATERIAL LIST

G1836C Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	137.13	16"	71	EA
2	MAIN TREATED SILL		2X4			95	LF
3	MAIN INT PLATES		2X4			12	LF
4	MAIN EXT PLATES		2X6			196	LF
5	MAIN INT STUDS		2X4		16"	6	EA
6	HEADER, (Ext Main Garage Door)	N/A	4X12	11'		1	EA
7	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
8	HEADER, (Main Window)	N/A	4X8	4'		1	EA
9	TRUSSES				24"	17	EA
10	TRUSSES (Ends)					2	EA
11	EAVE BLOCKING		2X	22.5"	24"	36	EA
12	H2.5 RAFTER TIE				24"	38	EA
13	ROOF SHEATH		1/2" CDX			801	SF
14	ROOF FELT		30# Felt			801	SF
15	ROOFING					801	SF
16	BARGE RAFTERS		2X6	11'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1188	SF
18	MAIN INT WALL S.R. (Optional)		1/2" GYP.			150	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			648	SF
20	EXT WALL SHEATH		1/2" CDX			1188	SF
21	EXT WALL VAPOR		15# Felt			1188	SF
22	EXT SIDING (See Plan)		Varies			1188	SF
23	CONCRETE (Footing)		12" X 20"			6.67	CY
24	CONCRETE (Floor)		4"			8.00	CY
25	ANCHOR BOLTS		1/2"		48"	24	EA
26	HOLD DOWNS		HD2A W/SSTB16			4	EA
27	WIRE MESH		6X6 W1.4 X W1.4			648	SF

22685 S.W. Conifer Dr. Sherwood OR 97140

Internet: www.cadnw.com Email: cadnw@zzz.com (503) 625-6330 Voice