

MATERIAL LIST

G2432B GARAGE PLAN

w/ attic truss

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	RAFTERS AT STAIR		2X6 DF#2	4'	24	8	EA
2	JOISTS AT STAIR		2X6 DF#2	4'	16	10	EA
3	JOISTS AT STAIR		2X12 DF#2	8'		1	EA
4	STAIR POST		4X4 DF#2	8'		2	EA
5	UPPER FLOOR SHEATHING		5/8" PLY			330	SF
6	STAIR STRINGER		2X12	12'		4	EA
7	LANDING FRAMING		2X6			21	LF
8	ATTIC TRUSSES		24' + O.H.		24"	14	EA
9	END TRUSSES		24' + O.H.			2	EA
10	GIRDER TRUSSES		24' + O.H.			1	EA
11	EAVE BLOCKING		2X4	22.5"		32	EA
12	RIDGE BLOCKING		2X4			32	LF
13	OUTLOOKERS		2X4			120	LF
14	GARAGE DOOR HEADER		4X12 DF#2	10'		2	EA
15	GARAGE DOOR HEADER (OPTION)		4X12 DF#2	17'		1	EA
16	MAIN DOOR HEADER		4X8 DF#2	4'		1	EA
17	MAIN WINDOW HEADER		4X10 DF#2	7'		1	EA
18	UPPER HEADER		4X8 DF#2	5'		2	EA
19	CONCRETE					14.87	CY
20	SHEET ROCK		1/2" GYP.			1585	SF
21	EXT WALL SHEATHING		1/2" CDX			1375	SF
22	EXT WALL VAPOR		15# FELT OR TYVEK			1375	SF
23	EXT SIDING		(SEE PLAN)			1375	SF
24	MAIN EXTERIOR STUDS		2X6 DF#2	8'		70	EA
25	MAIN EXTERIOR PLATES		2X6 DF#2			317	LF
26	MAIN EXTERIOR P.T. PLATE		2X6 DF#2			93	LF
27	STAIR RAILING		2X6			16	LF
28	STAIR RAILING		2X4			32	LF
29	PICKETS		2X2			48	EA
30	ROOF SHEATHING		1/2" CDX			1250	SF
31	ROOF FELT		30# FELT			1250	SF
32	ROOFING		(SEE PLAN)			1250	SF
33	FACIA		2X6			68	LF
34	BARGE RAFTERS		2X6			74	LF
35	ANCHOR BOLTS		1/2"		48	23	EA
36	ANCHOR BOLTS		SSTB16			5	EA
37	CLIPS		H2.5			34	EA
38	HOLD DOWNS		HD3B			5	EA
39	FRAMING ANCHOR		A23			16	EA

MATERIAL LIST

G2432B GARAGE PLAN

w/ framed roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	RIDGE BEAM	B01	5-1/8X15" 24F-V4 GLB	32'		1	EA
2	RAFTERS	B02	2X10 DF#2	20'	24	34	EA
3	COLLAR TIES (OPTION)		2X6 DF#2	8'	24	17	EA
4	JOISTS AT STAIR		2X6 DF#2	4'	16	10	EA
5	JOISTS AT STAIR		2X12 DF#2	8'		1	EA
6	JOISTS	TJI	16" TJI 360'S	24'		17	EA
7	RIM JOIST		1-1/4" X 16"			112	LF
8	POST		4X4 DF#2	8'		2	EA
9	POST		4X4 DF#2	10'		5	EA
10	POST		4X4 DF#2	12'		1	EA
11	STAIR POST		4X4 DF#2	8'		2	EA
12	STAIR BEAM POST		4X4 DF#2	10'		1	LF
13	UPPER FLOOR SHEATHING		5/8" PLY			768	SF
14	STAIR BEAM	B06	3-1/8X12 24F-V4 GLB	21'		1	EA
15	STAIR STRINGER		2X12	12'		4	EA
16	LANDING FRAMING		2X6			21	LF
17	EAVE BLOCKING		2X4	22.5"		32	EA
18	OUTLOOKERS		2X4			120	LF
19	GARAGE DOOR HEADER	B04	6X12 DF#2	10'		2	EA
20	GARAGE DOOR HEADER (OPTION)	B04B	5-1/8 X 13-1/2 24F-V4 GLB	17'		1	EA
21	MAIN DOOR HEADER		4X8 DF#2	4'		1	EA
22	MAIN WINDOW HEADER		4X10 DF#2	7'		1	EA
23	UPPER HEADER	B05	6X12 DF#2	5'		2	EA
24	CONCRETE					15.10	CY
25	SHEET ROCK		1/2" GYP.			1585	SF
26	EXT WALL SHEATHING		1/2" CDX			1375	SF
27	EXT WALL VAPOR		15# FELT OR TYVEK			1375	SF
28	EXT SIDING		(SEE PLAN)			1375	SF
29	MAIN EXTERIOR STUDS		2X6 DF#2	8'		70	EA
30	MAIN EXTERIOR PLATES		2X6 DF#2			317	LF
31	MAIN EXTERIOR P.T. PLATE		2X6 DF#2			93	LF
32	UPPER EXTERIOR STUDS (OPT)		2X6 DF#2			91	LF
33	UPPER INTERIOR PLATES (OPT)		2X4 DF#2			192	LF
34	UPPER INTERIOR STUDS		2X4 DF#2	5'		48	EA
35	STAIR RAILING		2X6			16	LF
36	STAIR RAILING		2X4			32	LF
37	PICKETS		2X2			48	EA
38	ROOF SHEATHING		1/2" CDX			1250	SF
39	ROOF FELT		30# FELT			1250	SF
40	ROOFING		(SEE PLAN)			1250	SF
41	FACIA		2X6			68	LF
42	BARGE RAFTERS		2X6			74	LF
43	ANCHOR BOLTS		1/2"		48	23	EA
44	ANCHOR BOLTS		SSTB16			5	EA
45	CLIPS		H2.5			34	EA
46	HOLD DOWNS		HD3B			5	EA
47	FRAMING ANCHOR		A23			16	EA
48	POST CAP		ECC64			2	EA
49	POST BASE		PB44			6	EA
50	STRAPS		LSTA18			8	EA