

MATERIAL LIST

G2436U Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	93.50	16"	75	EA
2	MAIN TREATED SILL		2X6			101	LF
3	MAIN INT PLATES		2X6			18	LF
4	MAIN EXT PLATES		2X6			344	LF
5	MAIN INT STUDS		2X6		16"	6	EA
6	HEADER, (Ext Main Garage Door)	B04-C	4X12	17'		1	EA
7	HEADER, (Ext Main Door)		4X8	4'		1	EA
8	HEADER, (Main Window)		4X10	7'		1	EA
9	HEADER, (Upper Window)		4X8	5'		1	EA
10	TRUSSES				24"	17	EA
11	TRUSSES (Ends)					2	EA
12	EAVE BLOCKING		2X	22.5"	24"	36	EA
13	H2.5 RAFTER TIE				24"	38	EA
14	ROOF SHEATH		1/2" CDX			1397	SF
15	ROOF FELT		30# Felt			1397	SF
16	ROOFING					1397	SF
17	BARGE RAFTERS		2X6	20'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			909	SF
19	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
20	MAIN CEILING S.R. (Optional)		1/2" GYP.			864	SF
21	EXT WALL SHEATH		1/2" CDX			1197	SF
22	EXT WALL VAPOR		15# Felt			1197	SF
23	EXT SIDING (See Plan)		Varies			1197	SF
24	CONCRETE					16.79	CY
25	ANCHOR BOLTS		1/2"		48"	26	EA
26	HOLD DOWNS		STHD10			4	EA
27	WIRE MESH		6X6 W1.4 X W1.4			864	SF

MATERIAL LIST

G2436U Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	93.50	16"	75	EA
2	MAIN TREATED SILL		2X6			101	LF
3	MAIN INT PLATES		2X6			18	LF
4	MAIN EXT PLATES		2X6			344	LF
5	MAIN INT STUDS		2X6		16"	6	EA
6	UPPER INT PLATES		2X4			216	LF
7	UPPER INT WALL STUDS		2X4	VARIES	16"	55	EA
8	UPPER CEILING S.R. (Optional)		1/2" GYP.			1222	SF
9	UPPER INT WALL S.R. (Optional)		1/2" GYP.			720	SF
10	HEADER, (Ext Main Garage Door)	B04-B	5-1/8X15 GLB	17'		1	EA
11	HEADER, (Ext Main Door)		4X8	4'		1	EA
12	HEADER, (Main Window)		4X10	7'		1	EA
13	HEADER, (Upper Window)	B05	6X12 DF#1	5'		1	EA
14	RAFTERS	B02	2X10	20'	24"	38	EA
15	EAVE BLOCKING		2X	22.0"	24"	36	EA
16	H2.5 RAFTER TIE				24"	38	EA
17	ROOF SHEATH		1/2" CDX			1397	SF
18	ROOF FELT		30# Felt			1397	SF
19	ROOFING					1397	SF
20	BARGE RAFTERS		2X6	20'		4	EA
21	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			909	SF
22	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
23	MAIN CEILING S.R. (Optional)		1/2" GYP.			864	SF
24	EXT WALL SHEATH		1/2" CDX			1197	SF
25	EXT WALL VAPOR		15# Felt			1197	SF
26	EXT SIDING (See Plan)		Varies			1197	SF
27	CONCRETE					16.93	CY
28	JOISTS	TJI	16 TJI 360	24'	16"	26	EA
29	RIM JOIST					120	LF
30	UPPER FLOOR PLYWOOD		5/8"			864	SF
31	POST		4X4	54'		1	EA
32	RIDGE BEAM	B01	3-1/8X25-1/2 GLB	36'		1	EA
33	STAIR BEAM	B06	3-1/8X12 GLB	21'		1	EA
34	ANCHOR BOLTS		1/2"		48"	26	EA
35	HOLD DOWNS		STHD10			4	EA
36	WIRE MESH		6X6 W1.4 X W1.4			864	SF