

**MATERIAL LIST**

**G3030D Garage Plan**

**Standard W/ Truss Roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	113.5" (Varies)	16"	74	EA
2	MAIN TREATED SILL		2X6			99	LF
3	MAIN EXT PLATES		2X6			306	LF
4	HEADER, (Ext Main Garage Door)	B01	3-1/8X12 GLB	10'		2	EA
5	HEADER, (Ext Main Door)		4X8	4'		1	EA
6	HEADER, (Main Window)		4X8	7'		2	EA
7	HEADER, (Upper Window)		4X8	7'		2	EA
8	TRUSSES				24"	14	EA
9	TRUSSES (Ends)					2	EA
10	EAVE BLOCKING		2X	22.5"	24"	30	EA
11	H2.5 RAFTER TIE				24"	32	EA
12	ROOF SHEATH		1/2" CDX			1448	SF
13	ROOF FELT		30# Felt			1448	SF
14	ROOFING					1448	SF
15	BARGE RAFTERS		2X6	23'		4	EA
16	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			990	SF
17	MAIN CEILING S.R. (Optional)		1/2" GYP.			900	SF
18	WALL SHEATH		1/2" CDX			1440	SF
19	WALL VAPOR		15# Felt			1440	SF
20	SIDING (See Plan)		Varies			1440	SF
21	CONCRETE (Footing)		12" X 6"			2.22	CY
22	CONCRETE (Stem)		6" X 20"			3.70	CY
23	CONCRETE (Floor)		4"			11.11	CY
24	CONC. FOOTING, (Garage Door)		(4) 24" X 24" X 12" DP.			0.59	CY
25	CONC. FOOTING, (Doorway Slab)		(1) 48" X 48" X 4" DP.			0.20	CY
26	GIRDER TRUSS			30'		1	EA
27	ANCHOR BOLTS		1/2"		48"	25	EA
28	WIRE MESH		6X6 W1.4 X W1.4			11	SF