

MATERIAL LIST

G4030N Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	113.50	16"	83	EA
2	MAIN TREATED SILL		2X4			141	LF
3	MAIN INT PLATES		2X4			60	LF
4	MAIN EXT PLATES		2X4			394	LF
5	MAIN INT STUDS		2X4		16"	24	EA
6	UPPER EXT STUDS		2X4	91.00	16"	72	EA
7	UPPER EXT WALL PLATES		2X4			276	LF
8	UPPER CEILING S.R. (Optional)		1/2" GYP.			480	SF
9	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			736	SF
10	HEADER, (Ext Main Garage Door)	B04	4X12	11'		1	EA
11	HEADER, (Ext Main Garage Door)		4X12	9'		2	EA
12	HEADER, (Ext Main Door)		4X8	4'		1	EA
13	HEADER, (Ext Upper Door)		4X8	4'		1	EA
14	HEADER, (Main Window)		4X8	4'		7	EA
15	HEADER, (Upper Window)		4X8	4'		7	EA
16	TRUSSES (Ends)						EA
17	EAVE BLOCKING		2X			92	EA
18	H2.5 RAFTER TIE					96	EA
19	ROOF SHEATH		1/2" CDX			1417	SF
20	ROOF FELT		30# Felt			1417	SF
21	ROOFING					1417	SF
22	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1110	SF
23	MAIN INT WALL S.R. (Optional)		1/2" GYP.			600	SF
24	MAIN CEILING S.R. (Optional)		1/2" GYP.			1200	SF
25	EXT WALL SHEATH		1/2" CDX			2206	SF
26	EXT WALL VAPOR		15# Felt			2206	SF
27	EXT SIDING (See Plan)		Varies			2206	SF
28	CONCRETE					22.96	CY
29	JOISTS	B03	2X10	16'	16"	24	EA
30	UPPER FLOOR PLYWOOD		5/8"			1200	SF

MATERIAL LIST

G4030N Garage Plan

Standard W/ Framed Roof

31	BEAM	B01	5-1/8X18 GLB	30'		30	LF
32	POST		6X6	12'		3	EA
33	POST		4X4	10'		2	EA
34	POST		4X4	8'		6	EA
35	ANCHOR BOLTS		1/2"		48"	28	EA
36	HOLD DOWNS		HD2A W/SSTB16			4	EA
37	STRAPS		MST37			20	EA
38	WIRE MESH		6X6 W1.4 X W1.4			1200	SF
39	RAFTERS		2X6	10'		48	EA
40	RAFTERS	B02	2X8	14'		48	EA
41	BARGE RAFTERS		2X6	10'		4	EA
42	BARGE RAFTERS		2X6	14'		4	EA
43	RIDGE BEAM		2X8	30'		30	LF
44	LEDGER		2X10	60'		60	LF
45	COLLAR TIES		2X6	14'		24	EA