

MATERIAL LIST

G1220A Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	93.50	16"	39	EA
2	MAIN TREATED SILL		2X4			52	LF
3	MAIN EXT PLATES		2X4			183	LF
4	HEADER, (Ext Main Garage Door)	B01	4X12	13'		1	EA
5	HEADER, (Ext Main Door)	N/A	4X6	4'		1	EA
6	HEADER, (Main Window)	N/A	4X6	6'		1	EA
7	TRUSSES				24"	9	EA
8	TRUSSES (Ends)					2	EA
9	EAVE BLOCKING		2X	22.5"	24"	20	EA
10	H2.5 RAFTER TIE				24"	22	EA
11	ROOF SHEATH		1/2" CDX			329	SF
12	ROOF FELT		30# Felt			329	SF
13	ROOFING					329	SF
14	BARGE RAFTERS		2X6	9'		4	EA
15	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			468	SF
16	MAIN CEILING S.R. (Optional)		1/2" GYP.			240	SF
17	EXT WALL SHEATH		1/2" CDX			468	SF
18	EXT WALL VAPOR		15# Felt			468	SF
19	EXT SIDING (See Plan)		Varies			468	SF
20	CONCRETE					6.91	CY
21	ANCHOR BOLTS		1/2"		48"	13	EA
22	ANCHOR BOLTS		5/8"			2	EA
23	STRAPS		LSTA18			13	EA
24	STRAPS		LSTA24			2	EA
25	HOLD DOWNS		STHD14			4	EA
26	WIRE MESH		6X6 W1.4 X W1.4			240	SF

MATERIAL LIST

G1220A Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	93.50	16"	39	EA
2	MAIN TREATED SILL		2X4			52	LF
3	MAIN EXT PLATES		2X4			183	LF
4	UPPER CEILING S.R. (Optional)		1/2" GYP.			268	SF
5	HEADER, (Ext Main Garage Door)	B01	4X12	13'		1	EA
6	HEADER, (Ext Main Door)		4X6	4'		1	EA
7	HEADER, (Main Window)	N/A	4X6	6'		1	EA
8	RAFTERS	B02	2X6	9'	24"	22	EA
9	EAVE BLOCKING		2X	22.5"	24"	20	EA
10	H2.5 RAFTER TIE				24"	22	EA
11	ROOF SHEATH		1/2" CDX			329	SF
12	ROOF FELT		30# Felt			329	SF
13	ROOFING					329	SF
14	BARGE RAFTERS		2X6	9'		4	EA
15	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			468	SF
16	MAIN CEILING S.R. (Optional)		1/2" GYP.			240	SF
17	EXT WALL SHEATH		1/2" CDX			468	SF
18	EXT WALL VAPOR		15# Felt			468	SF
19	EXT SIDING (See Plan)		Varies			468	SF
20	CONCRETE (Footing)		12" X 6"			1.19	CY
21	CONCRETE (Stem)		6" X 20"			1.98	CY
22	CONCRETE (Floor)		4"			2.96	CY
23	JOISTS	B03	2X8	12'	24"	11	EA
24	UPPER FLOOR PLYWOOD		1/2"			240	SF
25	ANCHOR BOLTS		1/2"		48"	13	EA
26	ANCHOR BOLTS		5/8"			2	EA
27	STRAPS		LSTA18			13	EA
28	STRAPS		LSTA24			2	EA
29	HOLD DOWNS		STHD14			4	EA
30	WIRE MESH		6X6 W1.4 X W1.4			240	SF