

MATERIAL LIST

G1224A Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1		2X4	93.50	16"	45	EA
2		2X4			61	LF
3		2X4			208	LF
4		1/2" GYP.			322	SF
5	B01	4X12	12'		1	EA
6	N/A	4X6	4'		1	EA
7	B02	2X6	9'	24"	26	EA
8		2X	22.5"	24"	24	EA
9				24"	26	EA
10		1/2" CDX			391	SF
11		30# Felt			391	SF
12					391	SF
13		2X6	9'		4	EA
14		1/2" GYP.			549	SF
15		1/2" GYP.			288	SF
16		1/2" CDX			549	SF
17		15# Felt			549	SF
18		Varies			549	SF
19		12" X 6"			1.33	CY
20		6" X 20"			2.22	CY
21		4"			3.56	CY
22	B03	2X8	12'	24"	13	EA
23		1/2"			288	SF
24		1/2"		48"	16	EA
25		SSTB28			4	EA
26		SIMPSON SW22X8X4			2	EA
27		6X6 W1.4 X W1.4			288	SF

MATERIAL LIST

G1224A Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

MAIN FLOOR

		SIZE	LENGTH	SPACING	QTY	
1	EXT. STUD	2X4	102 (varies)	16	43	EA
2	TREATED SILL	2X4			56	LF
3	PLATES	2X4			208	LF
4	DOOR HEADER	4x12	12		1	EA
5	WALL S.R. (Optional)	1/2"			532	SF
6	CEILING S.R. (Optional)	1/2"			288	SF
7	WALL SHEATH	1/2"			568	SF
8	WALL VAPOR	15# Felt			568	SF
9	SIDING				568	SF
10	CONCRETE (Footing)	12"x20"			4.88	CY
11	CONCRETE (Floor)	4"			3.52	CY
12	TRUSSES (Roof)		12' + O.H.	24	13	EA
13	ROOF SHEATH	7/16"			604	SF
14	ROOF FELT	30# Felt			604	SF
15	ROOFING	Composition			604	SF
16	EAVE BLOCKING	2X4	22.5"	24	25	EA
17	H2.5 RAFTER TIE			24	26	EA
18	HD-2A				4	EA
19	SSTB-16				4	EA
20	LSTA18				4	EA