

**MATERIAL LIST**

**G1424A Garage Plan**

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	113.50	16"	48	EA
2	MAIN TREATED SILL		2X4			64	LF
3	MAIN EXT PLATES		2X4			219	LF
4	MAIN FLOOR PLYWOOD		5/8"			336	SF
5	UPPER CEILING S.R. (Optional)		1/2" GYP.			475	SF
6	HEADER, (Ext Main Garage Door)	B04	4X12	14'		1	EA
7	HEADER, (Ext Main Door)		4X8	4'		1	EA
8	HEADER, (Main Window)		4X10	6'		1	EA
9	HEADER, (Upper Window)	B05	4X10	4'		1	EA
10	TRUSSES				24"	11	EA
11	TRUSSES (Ends)					2	EA
12	EAVE BLOCKING		2X	22.5"	24"	24	EA
13	H2.5 RAFTER TIE				24"	26	EA
14	ROOF SHEATH		1/2" CDX			588	SF
15	ROOF FELT		30# Felt			588	SF
16	ROOFING					588	SF
17	BARGE RAFTERS		2X6	12'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			640	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			336	SF
20	EXT WALL SHEATH		1/2" CDX			640	SF
21	EXT WALL VAPOR		15# Felt			640	SF
22	EXT SIDING (See Plan)		Varies			640	SF
23	CONCRETE					4.89	CY
24	UPPER FLOOR PLYWOOD		5/8"			336	SF
25	ANCHOR BOLTS		1/2"		48"	16	EA
26	HOLD DOWNS		HD2A W/SSTB16			4	EA

**MATERIAL LIST**

**G1424A Garage Plan**

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	113.50	16"	48	EA
2	MAIN TREATED SILL		2X4			64	LF
3	MAIN EXT PLATES		2X4			219	LF
4	MAIN FLOOR PLYWOOD		5/8"			336	SF
5	UPPER CEILING S.R. (Optional)		1/2" GYP.			475	SF
6	HEADER, (Ext Main Garage Door)	B04	4X12	14'		1	EA
7	HEADER, (Ext Main Door)		4X8	4'		1	EA
8	HEADER, (Main Window)		4X10	6'		1	EA
9	HEADER, (Upper Window)	B05	4X10	4'		1	EA
10	RAFTERS	B02	2X6	12'	24"	26	EA
11	EAVE BLOCKING		2X	22.0"	24"	24	EA
12	H2.5 RAFTER TIE				24"	26	EA
13	ROOF SHEATH		1/2" CDX			588	SF
14	ROOF FELT		30# Felt			588	SF
15	ROOFING					588	SF
16	BARGE RAFTERS		2X6	12'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			640	SF
18	MAIN CEILING S.R. (Optional)		1/2" GYP.			336	SF
19	EXT WALL SHEATH		1/2" CDX			640	SF
20	EXT WALL VAPOR		15# Felt			640	SF
21	EXT SIDING (See Plan)		Varies			640	SF
22	CONCRETE					4.89	CY
23	JOISTS	B03	2X10	14'	24"	13	EA
24	RIM JOIST					76	LF
25	UPPER FLOOR PLYWOOD		5/8"			336	SF
26	RIDGE BEAM	B01	3-1/8X16-1/2 GLB	24'		1	EA
27	ANCHOR BOLTS		1/2"		48"	16	EA
28	HOLD DOWNS		HD2A W/SSTB16			4	EA