

MATERIAL LIST

**G2420B Garage w/ Storage
w/ Framed Roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		CALC	SIZE	LENGTH	O.C.	QUANTITY	
1	EXT. STUD		2x4	93" (varies)	16	51	EA
2	TREATED SILL		2x4			67	LF
3	PLATES		2x4			255	LF
4	DOOR HEADER, Garage	B04	4X12	10		2	EA
5	WINDOW HEADER		4X12	7		1	EA
6	WALL S.R. (Optional)		1/2" GYP.			603	SF
7	CEILING S.R. (Optional)		1/2" GYP.			480	SF
8	FLOOR PLYWOOD		5/8"			480	SF
9	WALL SHEATH		1/2" CDX			891	SF
10	WALL VAPOR		15# Felt			891	SF
11	SIDING (See Plan)					891	SF
12	CONCRETE					10.27	CY
13	RAFTERS	BO2	2x10	20	24	22	EA
14	ROOF SHEATH		1/2"			809	SF
15	ROOF FELT		30# Felt			809	SF
16	ROOFING		Composition			809	SF
17	EAVE BLOCKING		2X8	22.5"	24	20	EA
18	H2.5 RAFTER TIE				24	21	EA
19	RIM JOISTS		2X14			88	LF
20	FLOOR JOISTS	TJI	16" TJI PRO 360's	24'	16	15	EA
21	RIDGE	B01	5-1/8x15 GLB	20'		1	EA
22	KNEE WALL STUDS (Opt.)		2X4	6'	16	62	EA
23	KNEE WALL PLATES (Opt.)		2X4			40	LF
24	WINDOW HEADER	B05	4X12	5'		1	EA
25	HD3B					5	EA
26	SSTB16					5	EA
27	STAIR BEAM	B06	3-1/8" X 12"	21'		1	EA

MATERIAL LIST

**G2420B Garage Plan
w/Truss Attic Standard Version**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		SIZE	LENGTH	O/C	QTY	
1	EXT. STUD	2x4	102" (Varies)	16	51	EA
2	TREATED SILL	2x4			67	LF
3	PLATES	2x4			255	LF
4	DOOR HEADER	4 X 12	10		2	EA
5	HEADER	4 X 12	11'		1	EA
6	WALL S.R. (Optional)	1/2"			603	SF
7	CEILING S.R. (Optional)	1/2"			480	SF
8	WALL SHEATH	1/2" CDX			891	SF
9	WALL VAPOR	15# Felt			891	SF
10	SIDING				891	SF
11	CONCRETE				10.27	CY
12	TRUSSES (Roof)		24' + O.H.	24	11	EA
13	ROOF SHEATH	1/2"			772	SF
14	ROOF FELT	30# Felt			772	SF
15	ROOFING	Composition			772	SF
16	EAVE BLOCKING	2X4	22.5"	24	21	EA
17	H2.5 RAFTER TIE			24	21	EA
18	HD3B				5	EA
19	SSTB16				5	EA