

**MATERIAL LIST**

**G2424BG Garage Plan**

**Standard W/ Truss Roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	108.00	16"	55	EA
2	MAIN EXT PLATES		2X6			272	LF
3	UPPER EXT STUDS		2X6	91.00	16"	72	EA
4	UPPER CEILING S.R. (Optional)		1/2" GYP.			607	SF
5	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			768	SF
6	HEADER, (Upper Window)	N/A	4X8	5'		4	EA
7	HEADER, (Ext Main Garage Door)	B02	4X12	17'		1	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
9	HEADER, (Main Window)	N/A	4X8	5'		1	EA
10	TRUSSES				24"	11	EA
11	TRUSSES (Ends)					2	EA
12	EAVE BLOCKING		2X	22.5"	24"	24	EA
13	H2.5 RAFTER TIE				24"	26	EA
14	ROOF SHEATH		1/2" CDX			826	SF
15	ROOF FELT		30# Felt			826	SF
16	ROOFING					826	SF
17	BARGE RAFTERS		2X6	15'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			666	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			576	SF
20	EXT WALL SHEATH		1/2" CDX			1434	SF
21	EXT WALL VAPOR		15# Felt			1434	SF
22	EXT SIDING (See Plan)		Varies			1434	SF
23	CONCRETE					13.43	CY
24	JOISTS	TJI	16 TJI 210	24'	16"	19	EA
25	RIM JOIST					96	LF
26	UPPER FLOOR PLYWOOD		5/8"			576	SF
27	ANCHOR BOLTS		1/2"		48"	19	EA
28	HOLD DOWNS		HD5A W/ SSTB20			8	EA
29	WIRE MESH		6X6 W1.4 X W1.4			576	SF