

**MATERIAL LIST**

**G2426M Garage Plan**

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	95.13	16"	59	EA
2	MAIN TREATED SILL		2X6			79	LF
3	MAIN EXT PLATES		2X6			182	LF
4	UPPER INT PLATES		2X4			156	LF
5	UPPER CEILING S.R. (Optional)		1/2" GYP.			750	SF
6	HEADER, (Ext Main Garage Door)	B04	4X12	10'		2	EA
7	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
8	HEADER, (Main Window)	N/A	4X12	7'		1	EA
9	HEADER, (Upper Window)	N/A	4X8	5'		1	EA
10	TRUSSES				24"	12	EA
11	TRUSSES (Ends)					2	EA
12	EAVE BLOCKING		2X	22.5"	24"	26	EA
13	H2.5 RAFTER TIE				24"	28	EA
14	ROOF SHEATH		1/2" CDX			1030	SF
15	ROOF FELT		30# Felt			1030	SF
16	ROOFING					1030	SF
17	BARGE RAFTERS		2X6	19'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			711	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			624	SF
20	EXT WALL SHEATH		1/2" CDX			999	SF
21	EXT WALL VAPOR		15# Felt			999	SF
22	EXT SIDING (See Plan)		Varies			999	SF
23	CONCRETE (Footing)		12" X 6"			1.85	CY
24	CONCRETE (Stem)		6" X 20"			3.09	CY
25	CONCRETE (Floor)		4"			7.70	CY
26	RIM JOIST					100	LF
27	UPPER FLOOR PLYWOOD					624	SF
28	ANCHOR BOLTS		1/2"		48"	20	EA
29	HOLD DOWNS		HD3B W/SSTB16			4	EA
30	WIRE MESH		6X6 W1.4 X W1.4			624	SF

**MATERIAL LIST**

**G2426M Garage Plan**

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	95.13	16"	59	EA
2	MAIN TREATED SILL		2X6			79	LF
3	MAIN EXT PLATES		2X6			182	LF
4	UPPER INT PLATES		2X4			156	LF
5	UPPER INT WALL STUDS		2X4	5'	16"	40	EA
6	UPPER CEILING S.R. (Optional)		1/2" GYP.			750	SF
7	HEADER, (Ext Main Garage Door)	B04	4X12	10'		2	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
9	HEADER, (Main Window)	N/A	4X12	7'		1	EA
10	HEADER, (Upper Window)	B05	3-1/8X10-1/2 GLB	5'		1	EA
11	RAFTERS	B02	2X10	19'	24"	24	EA
12	EAVE BLOCKING		2X	22.5"	24"	26	EA
13	H2.5 RAFTER TIE				24"	24	EA
14	ROOF SHEATH		1/2" CDX			1030	SF
15	ROOF FELT		30# Felt			1030	SF
16	ROOFING					1030	SF
17	BARGE RAFTERS		2X6	19'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			711	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			624	SF
20	EXT WALL SHEATH		1/2" CDX			999	SF
21	EXT WALL VAPOR		15# Felt			999	SF
22	EXT SIDING (See Plan)		Varies			999	SF
23	CONCRETE (Footing)		12" X 6"			1.85	CY
24	CONCRETE (Stem)		6" X 20"			3.09	CY
25	CONCRETE (Floor)		4"			7.70	CY
26	JOISTS	TJI	16 TJI 360	24'	16"	19	EA
27	RIM JOIST					100	LF
28	UPPER FLOOR PLYWOOD		5/8"			624	SF
29	RIDGE BEAM	B01	5-1/8X21 GLB	26'		1	EA
30	POST	N/A	4X4	3'		2	EA
31	POST	N/A	4X4	7'		2	EA
32	POST	N/A	4X4	9'		4	EA
33	STAIR BEAM	B06	3-1/8X12 GLB	21'		1	EA
34	ANCHOR BOLTS		1/2"		48"	20	EA
35	HOLD DOWNS		HD3B W/SSTB16			4	EA
36	WIRE MESH		6X6 W1.4 X W1.4			624	SF