

MATERIAL LIST

**G2430G Garage w/ Storage Above
Framed roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		CALC.	SIZE	LENGTH	DIST.	O.C.	QNTY.	
1	EXT. STUD (MAIN)		2x4	96" (varies)	89.00	16	67	EA
2	EXT. STUD (UPPER)		2x4	48" (varies)	60.00	16	46	EA
3	TREATED SILL		2x4		89.00		89	LF
4	PLATES		2x4		108.00		648	LF
5	DOOR HEADER, Garage	B04	5-1/8X15	17			1	EA
6	WINDOW HEADER		4X12	5			2	EA
7	WALL S.R. (Optional)		1/2" GYP.		89		1095	SF
8	CEILING S.R. (Optional)		1/2" GYP.				720	SF
9	FLOOR PLYWOOD		5/8"				720	SF
10	WALL SHEATH		1/2" CDX		89		1239	SF
11	WALL VAPOR		15# Felt		89		1239	SF
12	SIDING (See Plan)				89		1239	SF
13	CONCRETE (Footing)		12"x6"				2.00	CY
14	CONCRETE (Wall)		6" x 20"				3.33	CY
15	CONCRETE (Floor)		4"				8.80	CY
16	RAFTERS	BO2	2x10	17	30	24	32	EA
17	ROOF SHEATH		1/2"				1002	SF
18	ROOF FELT		30# Felt				1002	SF
19	ROOFING		Composition				1002	SF
20	EAVE BLOCKING		2X10	22.5"	60	24	30	EA
21	H2.5 RAFTER TIE				60	24	31	EA
22	RIM JOISTS		1 PLY 1-1/4" 0.8E		108		108	LF
23	FLOOR JOISTS	B03	16" TJI/PRO 360	24'	30	16	21	EA
24	RIDGE	B01	5-1/8x21 GLB	30'			1	EA
25	WINDOW HEADER	B05	3-1/8" X 12"	5'			1	EA
26	HD5A (See Plan)						2	EA
27	STAIR BEAM	B06	3-1/8" X 12"	21'			1	EA