

**MATERIAL LIST**

**G2432T Garage w/ Storage Above  
With Framed roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		CALC.	SIZE	LENGTH	O.C.	QNTY.	
1	EXT. STUD (MAIN)		2x6	96" (varies)	16	70	EA
2	EXT. STUD (UPPER)		2x6	48" (varies)	16	70	EA
3	TREATED SILL		2x6			93	LF
4	PLATES		2x6			672	LF
5	DOOR HEADER, Garage	B05	5-1/8X13-1/2	17		1	EA
6	WINDOW HEADER		4X8	5		2	EA
7	WALL S.R. (Optional)		1/2" GYP.			1144	SF
8	CEILING S.R. (Optional)		1/2" GYP.			768	SF
9	FLOOR PLYWOOD		5/8"			768	SF
10	WALL SHEATH		1/2" CDX			1288	SF
11	WALL VAPOR		15# Felt			1288	SF
12	SIDING (See Plan)					1288	SF
13	CONCRETE (Footing)		12"x6"			2.07	CY
14	CONCRETE (Wall)		6" x 20"			3.46	CY
15	CONCRETE (Floor)		4"			9.39	CY
16	RAFTERS	BO2	2" X 10"	17	24	34	EA
17	ROOF SHEATH		1/2"			1064	SF
18	ROOF FELT		30# Felt			1064	SF
19	ROOFING		Composition			1064	SF
20	EAVE BLOCKING		2" X 10"	22.5"	24	32	EA
21	H2.5 RAFTER TIE				24	33	EA
22	RIM JOISTS		1 PLY 1-1/4" 0.8E			112	LF
23	FLOOR JOISTS	B03	16" TJI/PRO 360	24'	16	23	EA
24	RIDGE	B01	5-1/8x22-1/2 GLB	32'		1	EA
25	WINDOW HEADER	B04	4" X 12"	4'		1	EA
26	HD5A HOLDDOWNS					1	EA
27	MST37 STRAPS					16	EA
28	STAIR BEAM	B06	3-1/8" X 12"	21'		1	EA