

MATERIAL LIST

G2440B Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	95.50	16"	81	EA
2	MAIN TREATED SILL		2X4			109	LF
3	MAIN INT PLATES		2X4			69	LF
4	MAIN EXT PLATES		2X6			368	LF
5	MAIN INT STUDS		2X4		16"	19	EA
6	UPPER EXT STUDS		2X6	91.00	16"	96	EA
7	UPPER INT PLATES		2X4			69	LF
8	UPPER CEILING S.R. (Optional)		1/2" GYP.			1040	SF
9	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			1024	SF
10	UPPER INT WALL S.R. (Optional)		1/2" GYP.			368	SF
11	HEADER, (Ext Main Garage Door)	B02	4X12	17'		1	EA
12	HEADER, (Ext Main Door)		4X8	4'		1	EA
13	HEADER, (Main Window)		4X10	7'		3	EA
14	HEADER, (Main Window)		4X8	5'		1	EA
15	HEADER, (Upper Window)		4X8	5'		2	EA
16	HEADER, (Upper Window)		4X10	7'		4	EA
17	TRUSSES				24"	19	EA
18	TRUSSES (Ends)					2	EA
19	EAVE BLOCKING		2X	22.5"	24"	40	EA
20	H2.5 RAFTER TIE				24"	42	EA
21	ROOF SHEATH		1/2" CDX			1183	SF
22	ROOF FELT		30# Felt			1183	SF
23	ROOFING					1183	SF
24	BARGE RAFTERS		2X6	15'		4	EA
25	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			981	SF
26	MAIN INT WALL S.R. (Optional)		1/2" GYP.			414	SF
27	MAIN CEILING S.R. (Optional)		1/2" GYP.			960	SF
28	EXT WALL SHEATH		1/2" CDX			2005	SF
29	EXT WALL VAPOR		15# Felt			2005	SF
30	EXT SIDING (See Plan)		Varies			2005	SF
31	CONCRETE					19.75	CY
32	JOISTS	B01, TJI	14 TJI 360	24'	16"	31	EA
33	RIM JOIST					128	LF
34	UPPER FLOOR PLYWOOD		5/8"			960	SF
35	GIRDER TRUSS			24'		1	EA
36	ANCHOR BOLTS		1/2"		48"	28	EA
37	WIRE MESH		6X6 W1.4 X W1.4			960	SF