

MATERIAL LIST

G2624A Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	95.13	16"	58	EA
2	MAIN TREATED SILL		2X6			78	LF
3	MAIN EXT PLATES		2X6			168	LF
4	HEADER, (Ext Main Garage Door)	B01	4X12	9'		2	EA
5	HEADER, (Ext Main Door)		4X8	4'		2	EA
6	HEADER, (Main Window)		4X8	7'		3	EA
7	TRUSSES (See Plan)				24"	12	EA
8	TRUSSES (Girder)					2	EA
9	EAVE BLOCKING		2X	22.5"	24"	26	EA
10	H2.5 RAFTER TIE				24"	28	EA
11	ROOF SHEATH		7/16" OSB			875	SF
12	ROOF FELT		30# Felt			875	SF
13	ROOFING					875	SF
14	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			702	SF
15	MAIN CEILING S.R. (Optional)		1/2" GYP.			624	SF
16	EXT WALL SHEATH		1/2" CDX			702	SF
17	EXT WALL VAPOR		15# Felt			702	SF
18	EXT SIDING (See Plan)		Varies			702	SF
19	CONCRETE (Footing)		12" X 6"			1.85	CY
20	CONCRETE (Stem)		6" X 20"			3.09	CY
21	CONCRETE (Floor)		4"			7.70	CY
22	DORMER, (Rafters)		2X6	5'		10	EA
23	DORMER, (Joists)		2X6	6'		5	EA
24	DORMER, (Ridge Beam)		2X8	9'		1	EA
25	ANCHOR BOLTS		5/8"		48"	20	EA
26	HOLD DOWNS		HD2A W/SSTB16			4	EA
27	WIRE MESH		6X6 W1.4 X W1.4			624	SF