

MATERIAL LIST

**G2630C Garage w/ Storage
w/framed Roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		CALC	SIZE	LENGTH	DIST.	O.C.	QUANTITY	
1	EXT. STUD		2X6	9' (varies)	91	16	69	EA
2	TREATED SILL		2X6		91		91	LF
3	PLATES		2X6		112		327	LF
4	DOOR HEADER, Garage	B04	3-1/8" X 9"	10			2	EA
5	WALL S.R. (Optional)		1/2" GYP.		91		910	SF
6	CEILING S.R. (Optional)		1/2" GYP.				780	SF
7	FLOOR PLYWOOD		5/8"				780	SF
8	WALL SHEATH		1/2" CDX		91		1192	SF
9	WALL VAPOR		15# Felt		91		1192	SF
10	SIDING (See Plan)				91		1192	SF
11	CONCRETE (Footing)		12"x6"				2.07	CY
12	CONCRETE (Wall)		6" x 20"				3.46	CY
13	CONCRETE (Floor)		4"				9.53	CY
14	RAFTERS	BO2	2x10	20	30	24	32	EA
15	ROOF SHEATH		1/2" CDX				1166	SF
16	ROOF FELT		30# Felt				1166	SF
17	ROOFING		Composition				1166	SF
18	EAVE BLOCKING		2X10	22.5"	60	24	30	EA
19	H2.5 RAFTER TIE				60	24	32	EA
20	RIM JOISTS		16"		112		112	LF
21	FLOOR JOISTS	TJI	TJI	26'	30	16	24	EA
22	RIDGE	B01	5-1/8x21 GLB	30'			1	EA
23	KNEE WALL STUDS (Opt.)		2X4	6'	60	16	92	EA
24	KNEE WALL PLATES (Opt.)		2X4		30		60	LF
25	WINDOW HEADER	B05	3-1/8" X 10-1/2"	4'			1	EA
26	HD2A (See Plan)						4	EA
27	SSTB16						4	EA
28	STAIR BEAM	B06	3-1/8" X 12"	24'			1	EA

MATERIAL LIST G2630C Garage Plan
w/Truss Attic Standard Version

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		SIZE	LENGTH	DISTANCE	O/C	QTY	
1	EXT. STUD	2x6	102" (Varies)	91.0	16	69	EA
2	TREATED SILL	2x6		91.0		91	LF
3	PLATES	2x6		112.0		327	LF
4	DOOR HEADER	4 X 12	10			2	EA
5	HEADER	4 X 12	4			1	EA
6	WALL S.R. (Optional)	1/2"		91		774	SF
7	CEILING S.R. (Optional)	1/2"				780	SF
8	WALL SHEATH	1/2" CDX		91.0		1112	SF
9	WALL VAPOR	15# Felt		91.0		1112	SF
10	SIDING			91.0		1112	SF
11	CONCRETE (Footing)	16" x 9"				3.04	CY
12	CONCRETE (Wall)	6" x 20"				3.46	CY
13	CONCRETE (Floor)	4"				9.53	CY
14	TRUSSES (Roof)		26' + O.H.	30	24	16	EA
15	ROOF SHEATH	1/2"				1228	SF
16	ROOF FELT	30# Felt				1228	SF
17	ROOFING	Composition				1228	SF
18	EAVE BLOCKING	2X4	22.5"	60	24	30	EA
19	H2.5 RAFTER TIE			60	24	32	EA
20	HD2A (See Plan)					4	EA
21	SSTB16					4	EA
22	WINDOW HEADER	3-1/8" X 10-1/2"		4'		1	EA