

**MATERIAL LIST**

**G3230B Garage Plan  
Truss Version**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

MAIN FLOOR

|    |                         | SIZE            | CALC. | LENGTH       | DISTANCE | SPACING | QUANTITY |    |
|----|-------------------------|-----------------|-------|--------------|----------|---------|----------|----|
| 1  | EXT. STUD               | 2X4             |       | 96" (Varies) | 101.00   | 16      | 76       | EA |
| 2  | TREATED SILL            | 2X4             |       |              | 131.00   |         | 131      | LF |
| 3  | PLATES                  | 2X4             |       |              | 154.00   |         | 446      | LF |
| 4  | DOOR HEADER             | 4X12            | B01   | 17           |          |         | 1        | EA |
| 5  | DOOR HEADER             | 4X8             |       | 4            |          |         | 1        | EA |
| 6  | WINDOW HEADER           | 4X8             |       | 5            |          |         | 1        | EA |
| 7  | WALL S.R. (Optional)    | 1/2"            |       |              | 161      |         | 1449     | SF |
| 8  | CEILING S.R. (Optional) | 1/2"            |       |              |          |         | 960      | SF |
| 9  | WALL SHEATH             | 1/2" CDX        |       |              | 101      |         | 1122     | SF |
| 10 | WALL VAPOR              | 15# Felt        |       |              | 101      |         | 1122     | SF |
| 11 | SIDING                  | (See Elevation) |       |              | 101      |         | 1122     | SF |
| 12 | CONCRETE (Footing)      | 12"x6"          |       |              |          |         | 2.30     | CY |
| 13 | CONCRETE (Floor)        | 4"              |       |              |          |         | 11.73    | CY |
| 14 | TRUSSES (Roof)          |                 |       | 32' + O.H.   | 30       | 24      | 16       | EA |
| 15 | ROOF SHEATH             | 1/2"            |       |              |          |         | 1213     | SF |
| 16 | ROOF FELT               | 30# Felt        |       |              |          |         | 1213     | SF |
| 17 | ROOFING                 | (See Elevation) |       |              |          |         | 1213     | SF |
| 18 | INTERIOR WALL           | 2X4             |       |              | 30       | 16      | 23       | EA |
| 19 | EAVE BLOCKING           | 2X4             |       | 22.5"        | 60       | 24      | 31       | EA |
| 20 | H2.5 RAFTER TIE         |                 |       |              | 60       | 24      | 32       | EA |
| 21 | HD2A W/ SSTB16          |                 |       |              |          |         | 2        | EA |