

MATERIAL LIST

G3624N Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	101.50	16"	69	EA
2	MAIN TREATED SILL		2X4			92	LF
3	MAIN INT PLATES		2X4			18	LF
4	MAIN EXT PLATES		2X4			285	LF
5	MAIN INT STUDS		2X4		16"	6	EA
6	HEADER, (Ext Main Garage Door)	N/A	4X12	10'		1	EA
7	HEADER, (Ext Main Garage Door)	N/A	4X12	9'		2	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
9	TRUSSES				24"	11	EA
10	TRUSSES (Ends)					2	EA
11	EAVE BLOCKING		2X	22.5"	24"	24	EA
12	H2.5 RAFTER TIE				24"	26	EA
13	ROOF SHEATH		1/2" CDX			1134	SF
14	ROOF FELT		30# Felt			1134	SF
15	ROOFING					1134	SF
16	BARGE RAFTERS		2X6	23'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			828	SF
18	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			864	SF
20	EXT WALL SHEATH		1/2" CDX			828	SF
21	EXT WALL VAPOR		15# Felt			828	SF
22	EXT SIDING (See Plan)		Varies			828	SF
23	CONCRETE (Footing)		12" X 20"			7.41	CY
24	CONCRETE (Floor)		4"			10.67	CY
25	ANCHOR BOLTS		1/2"		48"	23	EA
26	HOLD DOWNS		HD2A W/SSTB16			8	EA
27	WIRE MESH		6X6 W1.4 X W1.4			864	SF