

MATERIAL LIST

G3630E Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	103.13	16"	77	EA
2	MAIN TREATED SILL		2X4			103	LF
3	MAIN INT PLATES		2X4			12	LF
4	MAIN EXT PLATES		2X4			238	LF
5	MAIN INT STUDS		2X4		16"	6	EA
6	HEADER, (Ext Main Garage Door)	B01	6X12	11'		1	EA
7	HEADER, (Ext Main Garage Door)	B02	5-1/8X12 GLB	17'		1	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
9	TRUSSES				24"	17	EA
10	TRUSSES (Ends)					2	EA
11	EAVE BLOCKING		2X	22.5"	24"	36	EA
12	H2.5 RAFTER TIE				24"	38	EA
13	ROOF SHEATH		1/2" CDX			1327	SF
14	ROOF FELT		30# Felt			1327	SF
15	ROOFING					1327	SF
16	BARGE RAFTERS		2X6	18'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			927	SF
18	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			1080	SF
20	EXT WALL SHEATH		1/2" CDX			1040	SF
21	EXT WALL VAPOR		15# Felt			1040	SF
22	EXT SIDING (See Plan)		Varies			1040	SF
23	CONCRETE (Footing)		12" X 20"			8.15	CY
24	CONCRETE (Floor)		4"			13.33	CY
25	CONC. FOOTING, (Doorway Slab)		(1) 48" X 48" X 4" DP.			0.20	CY
26	ANCHOR BOLTS		1/2"		48"	26	EA
27	HOLD DOWNS		HD2A W/SSTB16			8	EA
28	WIRE MESH		6X6 W1.4 X W1.4			1080	SF