

MATERIAL LIST

G3828A Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	101.50	16"	76	EA
2	MAIN TREATED SILL		2X6			102	LF
3	MAIN INT PLATES		2X4			18	LF
4	MAIN EXT PLATES		2X6			369	LF
5	MAIN INT STUDS		2X4		16"	10	EA
6	HEADER, (Ext Main Garage Door)	B01-T	3-1/8X10-1/2 GLB	10'		3	EA
7	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
8	TRUSSES				24"	18	EA
9	TRUSSES (Ends)					2	EA
10	EAVE BLOCKING		2X	22.5"	24"	38	EA
11	H2.5 RAFTER TIE				24"	40	EA
12	ROOF SHEATH		1/2" CDX			1342	SF
13	ROOF FELT		30# Felt			1342	SF
14	ROOFING					1342	SF
15	BARGE RAFTERS		2X6	18'		4	EA
16	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			918	SF
17	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
18	MAIN CEILING S.R. (Optional)		1/2" GYP.			1064	SF
19	EXT WALL SHEATH		1/2" CDX			918	SF
20	EXT WALL VAPOR		15# Felt			918	SF
21	EXT SIDING (See Plan)		Varies			918	SF
22	CONCRETE					21.28	CY
23	ANCHOR BOLTS		1/2"		48"	26	EA
24	HOLD DOWNS		HD2A W/SSTB16			13	EA
25	WIRE MESH		6X6 W1.4 X W1.4			1064	SF

MATERIAL LIST

G3828A Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	101.50	16"	76	EA
2	MAIN TREATED SILL		2X6			102	LF
3	MAIN INT PLATES		2X4			18	LF
4	MAIN EXT PLATES		2X6			369	LF
5	MAIN INT STUDS		2X4		16"	10	EA
6	HEADER, (Ext Main Garage Door)	B01-F	3-1/8X9 GLB	10'		3	EA
7	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
8	RAFTERS	B02-F	2X10	18'	16"	59	EA
9	EAVE BLOCKING		2X	14.0"	16"	57	EA
10	H2.5 RAFTER TIE				16"	59	EA
11	ROOF SHEATH		1/2" CDX			1342	SF
12	ROOF FELT		30# Felt			1342	SF
13	ROOFING					1342	SF
14	BARGE RAFTERS		2X6	18'		4	EA
15	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			918	SF
16	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
17	MAIN CEILING S.R. (Optional)		1/2" GYP.			1064	SF
18	EXT WALL SHEATH		1/2" CDX			918	SF
19	EXT WALL VAPOR		15# Felt			918	SF
20	EXT SIDING (See Plan)		Varies			918	SF
21	CONCRETE					22.78	CY
22	JOISTS	B04-F	2X10	14'	16"	58	EA
23	RIDGE BEAM	B05-F	6-3/4X27 GLB	28'		1	EA
24	FLOOR BEAM	B03-F	6-3/4X27 GLB	28'		1	EA
25	ANCHOR BOLTS		1/2"		48"	26	EA
26	HOLD DOWNS		HD2A W/SSTB16			13	EA
27	WIRE MESH		6X6 W1.4 X W1.4			1064	SF
28	HANGERS		LUS210			40	EA