

MATERIAL LIST

G3828F Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	103.13	16"	77	EA
2	MAIN TREATED SILL		2X6			103	LF
3	MAIN TREATED SILL		2x4			25	LF
4	MAIN INT PLATES		2X4			50	LF
5	MAIN EXT PLATES		2X6			238	LF
6	MAIN INT STUDS		2X4		16"	20	EA
7	HEADER, (Ext Main Garage Door)	B01	4X12	10'		2	EA
8	HEADER, (Ext Main Garage Door)	B01	4X12	9'		1	EA
9	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
10	HEADER, (Main Window)	N/A	4X8	6'		1	EA
11	HEADER, (Main Window)	N/A	4X8	9'		1	EA
12	TRUSSES (See Plan)			28' + OH	24"	12	EA
13	TRUSSES (Ends)			28' + OH		2	EA
14	TRUSSES (See Plan)			25' + OH	24"	6	EA
15	TRUSSES (Ends)			25' + OH		1	EA
16	EAVE BLOCKING		2X	22.5"	24"	38	EA
17	H2.5 RAFTER TIE				24"	40	EA
18	ROOF SHEATH		1/2" CDX			1406	SF
19	ROOF FELT		30# Felt			1406	SF
20	ROOFING					1406	SF
21	BARGE RAFTERS		2X6	19'		3	EA
22	BARGE RAFTERS		2X6	17'		1	EA
23	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			927	SF
24	MAIN INT WALL S.R. (Optional)		1/2" GYP.			450	SF
25	MAIN CEILING S.R. (Optional)		1/2" GYP.			1064	SF
26	EXT WALL SHEATH		1/2" CDX			1188	SF
27	EXT WALL VAPOR		15# Felt			1188	SF
28	EXT SIDING (See Plan)		Varies			1188	SF
29	CONCRETE (Footing)		12" X 20"			8.15	CY
30	CONCRETE (Floor)		4"			13.14	CY
31	ANCHOR BOLTS		1/2"		48"	26	EA
32	HOLD DOWNS		HD2A W/SSTB16			6	EA
33	WIRE MESH		6X6 W1.4 X W1.4			1064	SF