

MATERIAL LIST

G4040A Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	121.13	16"	93	EA
2	MAIN TREATED SILL		2X6			125	LF
3	MAIN EXT PLATES		2X6			256	LF
4	UPPER CEILING S.R. (Optional)		1/2" GYP.			1923	SF
5	HEADER, (Ext Main Garage Door)	B01	8-3/4X16-1/2 GLB	17'		2	EA
6	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
7	HEADER, (Main Window)	N/A	4X8	5'		2	EA
8	TRUSSES		40' plus O.H.		24"	19	EA
9	TRUSSES (Ends)					2	EA
10	EAVE BLOCKING		2X4	22.5"	24"	40	EA
11	H2.5 RAFTER TIE				24"	42	EA
12	ROOF SHEATH		1/2" CDX			2171	SF
13	ROOF FELT		30# Felt			2171	SF
14	ROOFING					2171	SF
15	BARGE RAFTERS		2X6	27'		4	EA
16	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1313	SF
17	MAIN CEILING S.R. (Optional)		1/2" GYP.			1600	SF
18	EXT WALL SHEATH		1/2" CDX			1313	SF
19	EXT WALL VAPOR		15# Felt			1313	SF
20	EXT SIDING (See Plan)		Varies			1313	SF
21	CONCRETE (Footing)		12" X 20"			9.88	CY
22	CONCRETE (Floor)		4"			19.75	CY
23	CONC. FOOTING, (Garage Door)		(1) 32" X 32" X 14" DP.			0.31	CY
24	CONC. FOOTING, (Garage Door)		(1) 40" X 40" X 14" DP.			0.48	CY
25	CONC. FOOTING, (Garage Door)		(1) 64" X 32" X 14" DP.			0.61	CY
26	CONC. FOOTING, (Girder Support)		(1) 24" X 24" X 12" DP.			0.15	CY
27	UPPER FLOOR PLYWOOD		5/8" PLY			800	SF
28	POST		4X8	10'		4	EA
29	POST		4X6	10'		1	EA
30	ANCHOR BOLTS		1/2"		48"	32	EA
31	HOLD DOWNS		HD2A W/SSTB16			12	EA
32	WIRE MESH		6X6 W1.4 X W1.4			1600	SF