

**MATERIAL LIST**

**G5030B Garage Plan**

**Standard W/ Truss Roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	101.50	16"	90	EA
2	MAIN TREATED SILL		2X6			121	LF
3	MAIN INT PLATES		2X6			18	LF
4	MAIN EXT PLATES		2X6			444	LF
5	MAIN INT STUDS		2X6		16"	6	EA
6	HEADER, (Ext Main Garage Door)	B03	3-1/8X12 GLB	10'		4	EA
7	HEADER, (Ext Main Door)	B01	4X8	4'		1	EA
8	HEADER, (Main Window)		4X8	4'		4	EA
9	HEADER, (Upper Window)		4X8	4'		2	EA
10	TRUSSES				24"	14	EA
11	TRUSSES (Ends)					2	EA
12	EAVE BLOCKING		2X	22.5"	24"	30	EA
13	H2.5 RAFTER TIE				24"	32	EA
14	ROOF SHEATH		1/2" CDX			2166	SF
15	ROOF FELT		30# Felt			2166	SF
16	ROOFING					2166	SF
17	BARGE RAFTERS		2X6	35'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1089	SF
19	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
20	MAIN CEILING S.R. (Optional)		1/2" GYP.			1500	SF
21	EXT WALL SHEATH		1/2" CDX			2131	SF
22	EXT WALL VAPOR		15# Felt			2131	SF
23	EXT SIDING (See Plan)		Varies			2131	SF
24	CONCRETE (Footing)		12" X 20"			9.88	CY
25	CONCRETE (Stem)						CY
26	CONCRETE (Floor)		4"			18.52	CY
27	CONC. FOOTING, (Doorway Slab)		(1) 48" X 48" X 4" DP.			0.20	CY
28	ANCHOR BOLTS		1/2"		48"	31	EA
29	HOLD DOWNS		HD2A W/SSTB16			14	EA
30	WIRE MESH		6X6 W1.4 X W1.4			1500	SF