

**MATERIAL LIST**

**G5030D Garage Plan**

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	149.5" (Varies)	16"	90	EA
2	MAIN TREATED SILL		2X6			121	LF
3	MAIN EXT PLATES		2X6			372	LF
4	MAIN INT STUDS		2X4		16"	6	EA
5	MAIN INT PLATES		2X4			18	LF
6	HEADER, (Ext Main Garage Door)	B03	3-1/8X9 GLB	13'		3	EA
7	HEADER, (Ext Main Door)		4X8	4'		1	EA
8	HEADER, (Main Window)		4X8	7'		4	EA
9	TRUSSES				24"	24	EA
10	TRUSSES (Ends)					2	EA
11	EAVE BLOCKING		2X	22.5"	24"	50	EA
12	H2.5 RAFTER TIE				24"	52	EA
13	ROOF SHEATH		1/2" CDX			1844	SF
14	ROOF FELT		30# Felt			1844	SF
15	ROOFING					1844	SF
16	BARGE RAFTERS		2X6	18'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1573	SF
18	MAIN INT WALL S.R. (Optional)		1/2" GYP.			156	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			1500	SF
20	WALL SHEATH		1/2" CDX			1723	SF
21	WALL VAPOR		15# Felt			1723	SF
22	SIDING (See Plan)		Varies			1723	SF
23	CONCRETE (Footing)		12" X 20"			9.88	CY
24	CONCRETE (Stem)		6" X 24"			5.93	CY
25	CONCRETE (Floor)		4"			18.52	CY
26	CONC. FOOTING, (Garage Door)		(6) 18" X 18" X 12" DP.			0.50	CY
27	ANCHOR BOLTS		1/2"		48"	31	EA
28	HOLD DOWNS		HD2A W/SSTB16			8	EA
29	WIRE MESH		6X6 W1.4 X W1.4			1500	SF